QA/QC Checklist

PENNSTATE

	Ċ,	5	9
1	8	5	5
٩			,
		/	

Construction Services

DIVISION 26 – Electrical 26 23 00 – Low Voltage (<600V) Switchgear	General Information	Programming/ Design	Bidding/ Preconstruction	Installation/ Construction	Closeout/ Warranty		
01 General							
1. Verify that there is sufficient clearance in front of switchgear for draw-out breaker removal/installation.		\boxtimes		\boxtimes			
2. Switchgear shall have hinged doors on the front AND rear of the cabinets. The rear doors shall have a hasp for installation of a padlock. The rear doors shall be labeled to match the front.		\boxtimes		\boxtimes			
3. When switchgear arrives on site determine if breakers have been tested. It is better to test at time of delivery rather than after the switchgear is placed in service.				\boxtimes			
 During construction, OPP Utilities shall have access to electrical rooms or vaults where main switchgear is housed. A key should be issued to OPP Utilities or doors should be cored with a CS-UU core. 			\boxtimes	\boxtimes			
5. One spare breaker in each frame sized shall be provided.					\boxtimes		
6. Verify that the correct neutral ground bond is in place at the switchgear.		\square		\boxtimes			
7. Verify that the grounding electrode systems are properly in place (building, steel, water line, ground bed).		\boxtimes		\boxtimes			
02 Startup							
1. Switchgear will most likely be energized well in advance of the completion of the corresponding project. All energized devices shall be labeled.		\bowtie		\bowtie			
 Metering shall be in place when the switchgear is energized. In order to do this, the meter communication wire must be installed and properly landed. OPP Utilities will install the meter. Contact Dick Harris (<u>rsh3@psu.edu</u>; (814) 777-8742), OPP Utility Systems Engineer, and/or Kevin Hahn (<u>kxh22@psu.edu</u>; (814) 592-7145), OPP Supervisor Trades III Electrical Services to visit the site and review/approve the installation and coordinate the meter installation. 							
3. Training for OPP Utilities and the OPP Electrical Integrity crew shall be done as soon as possible after the gear is energized rather than wait until the end of the project.				\boxtimes	\boxtimes		
4. Switchgear shall be cleaned of construction debris prior to startup. Once switchgear is energized, the electric room shall be cleaned and excess materials shall be removed. The room air shall be filtered if construction dust will continue to be present.							
5. Once switchgear is energized, contractors shall follow NFPA 70E for arc flash protection.				\boxtimes			
Div 26 23 20 – Low Voltage Switchgear Page 1 of 2			01/15/2010 jlk29				

6. Switchgear cabinets should be opened and cleaned again if necessary at the completion of construction.			\square